

Storm Water Management and Cuts and Fills:

Best Practices for Johnson Heights Timber Harvest:

- Road Grade is laid out to conform to natural grade of the land, cut and fills will be minimal.
- Storm Water from new roadway will be directed to ditch and directed to runoff to vegetated areas and collection points.
- Silt fence and straw will be used as necessary to protect from runoff going into the Highland Hills irrigation ditch.
- Slash Pads will be used to protect from soil exposure where equipment is operating.
- Bare soils in the ditches will be covered with seed and straw at the completion of the timber harvest.
- Bare soils in Landing areas will be covered with straw at the completion of the timber harvest.